

## Addendum 1

### 1. Clarification to the Scope of Work for the Airport Lighting Extension

In the quoted prices you will included all labour, installation, earth works, and construction materials associated with the installation of the complete lighting system including the installation of the cement pile for the elevated structure including the supply and erection. The top height of the elevated light structure (Drawing 7) will be 6 feet (1.8 Meters) approve grade. (The use of other brands and/or fabrication companies for the supplying of the elevated structure including any connector and couplers to be included).


For the LED lighting system, the use of a dual power supply will be required as the system is close to maximum now with current power supply; therefore, a new DCR Supply-Double-Arcal will need to be included in the scope.

The quotation is to include a turnkey LED Approach Lighting System including all hardware, materials and installation. Provided is a materials list of (but not limited to) for the Lighting, Hardware and Installation Requirements.

<b>Lighting</b>	<b>Counts/Units</b>
Pearl Approach - White	45
Pearl Approach - Green	11
DCR Supply - Double - Arcal	1
Frangible Couplings OD (2 Inch)	29
Other Connectors, Electrical Parts and Materials	1 Lot
<b>Hardware</b>	<b>Counts/Units</b>
Approach Lighting Mounts	1 - Lot
Stakes c/w Head and Lug	11
Tripods	18
Airfield Cabling # 12	2000 Feet
Secondary Cabling Various Lengths	1 - Lot
Electrical Conn Boxes	20
<b>Installation</b>	<b>Counts/Units</b>
Engineered Drawings	1 Set
Operating Manual	1 Set
Survey	1

Electrician	1
Trenching	2500 - Feet
Screw Piles	18
Cement Pile (For Elevated Structure)	1
Conduit - 3 Inch	2500 - Feet
Technician (Project Manager)	1

2. The Closing date and time for the Submission of the RFP's will be extended to July 24, 2019 at 2:00 PM.



---

Dave McPhee  
Manager of Transportation Services